



# Beam commissioning and operation status of LEAF

**Yao Yang**

On behalf of LEAF team

Institute of Modern Physics (IMP),  
Chinese Academy of Sciences, Lanzhou, China



- **Brief Introduction**
- **LEAF beam commissioning**
- **Beam energy adjustment system**
- **LEAF-AMS**
- **Summary**



## HIAF

**H**igh **I**ntensity heavy ion **A**ccelerator  
**F**acility



### □ Nuclear physics research


- ✓ to explore the limit to the existence of nuclei in terms of proton and mass numbers
  - ✓ to find exotic nuclear structure and study the physics behind
  - ✓ to understand the origin of the heavy elements in the cosmos
  - ✓ to depict the QCD phase diagram of nuclear matter, etc
- Total budget: 2.8 B CNY ¥ (424 M USD \$)
- **Schedule: 2018-2025**
- **Construction started officially Dec. 2018**
- Located in Huizhou City of Guangdong Province in south China

# 3 Brief introduction of HIAF



## External target station


- Nuclear Matter
- Hyper-nuclear
- High-E irradiation



**BRing**  
Fast cycle ring  
Circumference: 569 m  
Rigidity: 34 Tm


**HFRS: RIB line**  
L: 192m, Bp: 25 Tm

## RIB Physics station




**SRing**  
High precision spectrometer ring  
Circumf. 277 m, Rigidity: 15 Tm

	FE	iLinac	BRing	HFRS	SRing
Energy (MeV/u)	0.8 (U <sup>35+</sup> )	17 (U <sup>35+</sup> )	835 (U <sup>35+</sup> )	800 (U <sup>92+</sup> )	800 (U <sup>92+</sup> )
Intensity	28 $\mu$ A (U <sup>35+</sup> )	28 $\mu$ A (U <sup>35+</sup> )	2*10 <sup>11</sup> ppp (U <sup>35+</sup> )	--	10 <sup>10</sup> PPP (U <sup>92+</sup> )
Operation mode	CW or pulse	CW or pulse	Fast ramping 12T/s 3Hz	Momentum resolution 1100	DC, deceleration



**iLinac: Superconducting linac**  
Energy: 17MeV/u ( <sup>238</sup>U<sup>35+</sup> )  
Intensity: 28  $\mu$ A



**Low energy nuclear structure and irradiation terminal**

## RT Front End


Energy: 0.8MeV/u  
Intensity: **28  $\mu$ A** ( <sup>238</sup>U<sup>35+</sup> )



✓ Prototype of HIAF Front-End

✓ User facility

- *Low energy nuclear astrophysics*
- *Material irradiation*
- *material property fast evaluation*
- *X-ray spectrometry with very high charge state ions*



- *Launched at IMP in 2015*
- *RFQ assembled in Dec. 2017 and RF conditioning finished in Feb. 2018*
- *First beam in May 2018*
- *Beam energy adjustment system: from 2019 to 2021*




- ✓ FECR will be installed on LEAF by the end of this year
- ✓ A 28 GHz super-conducting ECR source SECRAI is used for commissioning

Zhao's talk in IPAC'22 and this conference


FECR key parameters

Microwave	45 GHz/20 kW
Magnet conductor	Nb <sub>3</sub> Sn
Axial field [T]	6.5/1.0/3.5
Sextupole field [T]	<u>3.8@r=75 mm</u>
Maximum field [T]	11.8 T
Maximum stress [Mpa]	150
Magnet bore [mm]	>Φ160
Stored energy [MJ]	1.6
Extraction voltage [kV]	50
Typical beam	1.0 emA U <sup>35+</sup>






Duty cycle	100%
Operating frequency (MHz)	81.25
Resonant cavity	4-vane
Input particle energy (keV/u)	14
Output particle energy (keV/u)	70 (M/q=7)
Max. Vane voltage (kV)	60 (M/q=7)
CW RF power (kW)	1.57 Kilpatrick units
Peak field at electrode surface	~596.4
Length	




33 hr, operation with full rf power






- ✓ Ion M/q=2~7
- ✓ Beam current~100 eμA
  - Transmission efficiency > 97%
  - Acceleration efficiency > 85% (with Pre-buncher, operation with two frequencies, RFQ fundamental and sub-harmonic)
  - Good agreement between the measurements and simulations


- Y. Yang, et al. *Phys. Rev. Accel. Beams* 22, 110101 (2019)



## LEA Beam Diagnostics GUI






- Transverse Emittance & Profile [FC]
- Longitudinal Bunch Length [FFC]
- Beam Position & Phase [BPM]
- Beam Energy [BPM]
- Energy Spectrum [Silicon]






- ✓ MHB operates with two frequencies (RFQ fundamental and sub-harmonic)




- Yao Yang, *et al*, *Nuclear Inst. and Methods in Physics Research, A* 1029 (2022) 166457




- Three-gradient technique
- The measured emittances are systematically 1.2~1.4 times lower than those expected from simulations due to the methodic error
- Lower emittance with the MHB operating with the RFQ fundamental frequency by lowering the bunch charge

- $\text{Ar}^{9+}$  1.2 mA from source
- Without LEPT collimator
- Accelerated current: 733  $\mu\text{A}$
- RFQ transmission  $\sim 72.4\%$





- ✓ With LEPT collimators
- ✓ Half of the current removed
- ✓ RFQ transmission  $>90\%$
- ✓ Accelerated current: 410  $\mu\text{A}$








- Ion source current : **690  $\mu\text{A}$**
- Drain current: 10.3  $\mu\text{A}$
- $\epsilon_{xx'}$ : 0.23  $\pi\cdot\text{mm}\cdot\text{mrad}$
- $\epsilon_{yy'}$ : 0.18  $\pi\cdot\text{mm}\cdot\text{mrad}$



- Ion source current : **1370  $\mu\text{A}$**
- Drain current: 19.9  $\mu\text{A}$
- $\epsilon_{xx'}$ : 0.43  $\pi\cdot\text{mm}\cdot\text{mrad}$
- $\epsilon_{yy'}$ : 0.36  $\pi\cdot\text{mm}\cdot\text{mrad}$






How to maintain beam quality while increasing the current is an important task!




## Uncertain Cross section at stellar energies


- Beck, Mukhamedzhanov and Tang, Eur. Phys. J. A (2020) 56:87
- Mukhamedzhanov, Kadyrov and Pang, Eur. Phys. J. A (2020) 56:233



- Large difference between THM and Hindrance  $\rightarrow$  Highly uncertain rate
- INDIRECT: Corrected THM exhibits a trend similar to Hindrance by replacing PWIA with DWIA
- Unknown resonances
  - $^{12}\text{C}(^{12}\text{C}, p)^{23}\text{Na}$  ( $Q=2.24$  MeV)
  - $^{12}\text{C}(^{12}\text{C}, \alpha)^{20}\text{Ne}$  ( $Q=4.62$  MeV)
  - $^{12}\text{C}(^{12}\text{C}, n)^{23}\text{Mg}$  ( $Q=-2.62$  MeV)


LEAF, which can provide a high intensity of  $^{12}\text{C}$  beam up to 100  $\mu\text{A}$ , will be an ideal platform to measure cross sections of  $^{12}\text{C}+^{12}\text{C}$  reaction at astrophysical energies if it could provide a broad beam energy variation of 0.3~0.7 MeV/u with carbon ions while maintaining energy spread







Basic design specifications of the DTL

Duty cycle	100%
Operating frequency (MHz)	81.25
Number of gaps	8
Design ion M/Q	4
Input particle energy (MeV/u)	0.5
Output particle energy (MeV/u)	0.3~0.7
Max. gap voltage (kV)	195
Q factor	11928
Peak field (Kilpatrick units)	1.43
Max. RF power (kW)	~18.6
Tube length (mm)	32
Gap (mm)	25.96
Drift tube inner diameter (mm)	40
Cavity length (mm)	~563.7
Cavity diameter (mm)	~910.6








- Measurements agree well with simulations, demonstrating continuously adjustable energy in the range of 0.3-0.7 MeV/u
- Measured energy spread  $\sim 0.11\% (1\sigma)$

• **Y. Yang**, et al, *Nuclear Inst. and Methods in Physics Research*, A 1039 (2022) 167095



## Trace actinide detection



- Efficient production of high-charge state ions ensures the **elimination of molecular ions** at the source stage


# Preliminary results-**detection of Uranium**




- Detection of  $^{234}\text{U}$
- $^{234}\text{U}^{34+}$  ions were selected from the source

- Pilot beam:  $^{131}\text{Xe}^{19+}$   $^{206}\text{Pb}^{30+}$  ( $\Delta(M/q)/(M/q) \sim 0.0009$ )

d	$^{131}\text{Xe}^{19+} + ^{131}\text{Xe}^{19+}$
e	$^{131}\text{Xe}^{19+} + ^{206}\text{Pb}^{30+}$
f	$^{131}\text{Xe}^{19+} + ^{234}\text{U}^{34+}$
g	$^{206}\text{Pb}^{30+} + ^{206}\text{Pb}^{30+}$
h	$^{206}\text{Pb}^{30+} + ^{234}\text{U}^{34+}$



- ✓ Successful to detect and identify Uranium isotopes and interferences
- ✗ Measurement of isotopic abundance  $^{234}\text{U}/\text{U}$  is still being explored





- As the prototype of HIAF Front-End, LEAF has been constructed and successfully commissioned. Key performance parameters demonstrated.
- High transmission efficiencies (typically higher than 97%) were relatively easy to achieve for beam currents of  $\sim 100$   $\mu\text{A}$  level. However, while beam current goes to several hundred  $\mu\text{A}$  or  $\text{mA}$  level, the transmission efficiency of the RFQ is gradually reduced because of degraded beam quality.
- A setup of ion beam energy adjustment system has been developed, precise beam energy tuning with  $0.3\sim 0.7$   $\text{MeV/u}$  has been achieved, and more than  $50$   $\mu\text{A}$  carbon beam with an energy spread of  $\sim 0.11\%$  ( $1\sigma$ ) has been delivered to the experimental terminal.
- Accelerator Mass Spectrometry has been developed based on LEAF, preliminary detection of Uranium was implemented, feasibility demonstrated.

**Thanks for your attention**  
and for your patience in listening to the remote speaker!

[yangyao@impcas.ac.cn](mailto:yangyao@impcas.ac.cn)