



#### 国家重大科技基础设施-加速器驱动嬗变研究装置

# Status and Challenges of NbCu SRF Cavities for Superconducting Linac

Mengxin Xu IMP Linac Center Aug 30 2022







## **1. Introduction**

## **2.** Copper Niobium Cavity

**3.** Summary and Outlook









**Given Service and Service And** 

## Main structure

- Superconducting drive linac
  - □ 500MeV, 5mA
- □ Spallation target
  - **Pb-Bi**, 2.5MW
- Subcritical reactor
  - **10MW**
- Total Budget about 400M \$
  Schedule:2021~2027





# Introduction







# Introduction



## **CiADS** Linac Design



Sections	Frequency(MHz)	beta	Cryomodules	Cavities	Solenoids
HWR010	162.5	0.1	1	9	9
HWR019	162.5	0.19	4	24	24
HWR040	325	0.4	10	60	20
Ellipt062	650	0.62	10	30	0
Ellipt082	650	0.82	7	28	0
Totals			32	151	53





# Introduction



## **Cavities Parameters**





Parameters	Unit	HWR010	HWR019	HWR040	Elliptical062-6cell	Elliptical082-5cell
Beta		0.10	0.19	0.40	0.62	0.82
frequency	MHz	162.50	162.50	325.00	650.00	650.00
Beam Aperture	mm	40.00	40.00	50.00	100.00	100.00
Leff	m	0.185	0.351	0.369	0.821	0.896
L <sub>ftof</sub> (flange to flange)	m	0.2100	0.4700	0.4500	1.2200	1.2200
Ep/Eacc		5.71	4.24	3.83	2.78	2.14
Bp/Eacc	mT/MV/m	12.52	6.21	7.35	4.83	4.04
Ep(operation)	MV/m	26.00	28.00	28.00	29.00	29.00
Вр @Ер	mT	57.01	41.01	53.73	50.38	54.75
TTF		0.83	0.8871	0.82	0.73	0.73
Veff@Ep	[MV]	0.84	2.32	2.70	8.56	12.15
V0 @Ep	[MV]	1.01	2.61	3.29	11.73	16.64
Eacc @Ep	[MV/m]	4.55	6.60	7.31	10.43	13.55
U @Ep	J	4.54	15.68	13.02	54.34	73.61
G	Ohm	28.00	66.43	106.80	188.00	229.00
R/Q	Ohm	158.33	337.22	244.60	330.00	501.00
			1			











### **Reliability of CiADS facility: beam trips is emphasized**

- Electricity on the external grid, less than 3/y (beam trip time >5min)
- $\Box$  Thermal shock on the beam window, less than 25000/y(beam trip time <1s)
- $\Box$  Thermal shock on the reactor, less than 2500/y(1s<br/>beam trip time <10s), less than 250/y(10s<br/>beam trip time <5min)

## **Status of CaFe linac**

- □ 4 cryomodules
- □ 4K operation
- □ Trip about 1 time per hour







# **Robust Superconducting Cavity**



## **Thicker cavity wall**

- **Local helium contacted with cavity**
- **Shield the external vibrations**







- Cu/Nb Cavity
- **Save niobium cost**
- **High thermal stability**
- **High mechanical stability**
- Previous two major technology
  - Sputtering niobium on copper cavity(micro niobium): CERN's LEP, 274 cavities, 4cell, 352MHz; INFN's 54 QWR cavities
  - Cu/Nb Explosive sheet(2mm niobium+8mm copper):JAERI's QWR cavities

## **IMP's Cu/Nb Cavity development**

- Developing sputteing niobium on copper since 2015
- □ Cu/Nb sheet fabrication :Explosive, HIP
- Coating Copper on Nb cavity
- Casting Copper on Nb cavity



# **Thin-shell cavity**



- Fabrication cavity with 1mm thickness niobium
- **1/3 material cost**
- **Fabrication processing not change much**
- Improved heat exchange
- □ Niobium cavity's surface processing still can be used
- **4** single cell cavity have been completed and two of them be tested
- □ Now, fabricating 1mm HWR cavity are developing







# **Coating Copper on niobium cavity**



**Coating 4~5mm copper on the outside of thin niobium cavity** 

- **Improved mechanical stability**
- **Enhanced the thermal performance for using local cooling**











- **Comparing to coating copper**
- **Casting copper shows impressive higher thermal conductivity**
- **Shorter fabrication time**
- **There is some issues still work on**



LINAC22\_TU1AA01\_Mengxin



# **Cavity Simulation**



## **Thermal Simulation**

- Local helium cooling
- □ 0.2 K temperature arising

## Mechanical Simulation

□ Stiffness 10KN/mm

□ Adjusting the thickness of cavity is flexible for optimizing mechanical stability

		HWR010	HWR019	HWR040
3mm niobium	LFD [Hz/(MV/m)^2]	-5.5	-5	-7
	df/dp [Hz/mbar]	-10.5	-1	-35
6mm(Cu/Nb)	LFD [Hz/( $MV/m$ )^2]	-4	-0.92	1.23
	df/dp [Hz/mbar]	-0.08	0.71	2.28



#### LINAC22\_TU1AA01\_Mengxin

റ



# **Engneering Design**



HWR section's design have been completed
Ellipitical section's design still going on









# **Niobium cavity fabrication**



# 9 HWR0105 deliver to lanzhou4 final EBW



# 24 HWR019

## HWR040(1mm)

**6** are preparing for final EBW part fabrication











- **The coupler have been delivered two for testing**
- **Tuner are under testing**
- Integration testing vessel have been ready
- **Cavity is doing final coating processing**







- **Appling Cu/Nb** cavity technology in CiADS is a critical decision
- **Different type of Cu/Nb cavity are developing**
- New engineering design have been conducted to cooperate with the Cu/Nb cavity technology
- **HWR010** cryomodule is planed assembly in the end of this year





# Thank you for your attentions!

